

AD-A074 648


NEW YORK STATE DEPT OF ENVIRONMENTAL CONSERVATION ALBANY F/G 13/2  
NATIONAL DAM SAFETY PROGRAM. NANTICOKE CREEK WATERSHED PROJECT --ETC(U)  
FEB 79 6 KOCH


DACW51-79-C-0001

NL

UNCLASSIFIED

| OF |  
ADA  
074648





SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM								
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER								
4. TITLE (and Subtitle) Phase I Inspection Report Nanticoke Creek Watershed Project Site 8 Susquehanna River Basin, Broome County, New York Inventory No. N.Y. 573		5. TYPE OF REPORT & PERIOD COVERED Phase I Inspection Report National Dam Safety Program								
7. AUTHOR(s)  George Koch, P.E.		6. PERFORMING ORG. REPORT NUMBER								
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)  DACW-51-79-C-0001								
11. CONTROLLING OFFICE NAME AND ADDRESS  New York State Department of Environmental Conservation/ 50 Wolf Road Albany, New York 12233		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS								
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)  Department of the Army 26 Federal Plaza/ New York District, CofE New York, New York 10007		12. REPORT DATE 17 April 1979								
		13. NUMBER OF PAGES								
		15. SECURITY CLASS. (of this report)  UNCLASSIFIED								
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE								
16. DISTRIBUTION STATEMENT (of this Report)  Approved for public release; Distribution unlimited.										
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)										
18. SUPPLEMENTARY NOTES										
19. KEY WORDS (Continue on reverse side if necessary and identify by block number)										
<table border="0"> <tr> <td>Dam Safety</td> <td>Nanticoke Creek Watershed Project</td> </tr> <tr> <td>National Dam Safety Program</td> <td>Broome County</td> </tr> <tr> <td>Visual Inspection</td> <td>Susquehanna River Basin</td> </tr> <tr> <td>Hydrology, Structural Stability</td> <td>Nanticoke Creek</td> </tr> </table>			Dam Safety	Nanticoke Creek Watershed Project	National Dam Safety Program	Broome County	Visual Inspection	Susquehanna River Basin	Hydrology, Structural Stability	Nanticoke Creek
Dam Safety	Nanticoke Creek Watershed Project									
National Dam Safety Program	Broome County									
Visual Inspection	Susquehanna River Basin									
Hydrology, Structural Stability	Nanticoke Creek									
20. ABSTRACT (Continue on reverse side if necessary and identify by block number)										
<p>This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization.</p> <p>Nanticoke Creek Watershed Protection Project Dam Site No. 8 was found to have no conditions which would render the dam unsafe. Minor maintenance actions were recommended.</p>										

A074648

DDC FILE COPY

LEVEL II

D D C  
RECEIVED  
OCT 1979  
RECEIVED  
E

SUSQUEHANNA RIVER BASIN  
NANTICOKE CREEK WATERSHED PROJECT  
SITE 8  
BROOME COUNTY, NEW YORK  
INVENTORY NO. NY 573

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

Nanticoke Creek Watershed Project Site Number 8  
(Inventory Number NY-573). Susquehanna  
River Basin. Broome County, New York.  
Phase 1 Inspection Report.



10 George /Koch

15 DACW51-79-C-0001

APPROVED FOR PUBLIC RELEASE  
DISTRIBUTION UNLIMITED  
CONTRACT NO. DACW51-79-C0001

12 74



SUSQUEHANNA RIVER BASIN  
NANTICOKE CREEK WATERSHED PROTECTION  
PROJECT SITE No. 8  
I.D. No. NY-573 (# 85D-3645)  
PHASE 1 INSPECTION REPORT

TABLE OF CONTENTS

	<u>PAGE NO.</u>
- ASSESSMENT	
- OVERVIEW PHOTOGRAPH	
1 PROJECT INFORMATION	1
1.1 GENERAL	1
1.2 DESCRIPTION OF PROJECT	1
1.3 PERTINENT DATA	2
2 ENGINEERING DATA	4
2.1 DESIGN	4
2.2 CONSTRUCTION RECORDS	4
2.3 OPERATION RECORD	4
2.4 EVALUATION OF DATA	4
3 VISUAL INSPECTION	5
3.1 FINDINGS	5
3.2 EVALUATION OF OBSERVATIONS	6
4 OPERATION AND MAINTENANCE PROCEDURES	7
4.1 PROCEDURE	7
4.2 MAINTENANCE OF DAM	7
4.3 WARNING SYSTEM IN EFFECT	7
4.4 EVALUATION	7

Accession For	
NTIS Grant	<input checked="" type="checkbox"/>
DDO TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/ _____	
Availability Codes	
Dist	Avail and/or special
A	

	<u>PAGE NO.</u>
5 HYDROLOGIC/HYDRAULIC	8
5.1 DRAINAGE AREA CHARACTERISTICS	8
5.2 ANALYSIS CRITERIA	8
5.3 SPILLWAY CAPACITY	8
5.4 RESERVOIR CAPACITY	8
5.5 FLOODS OF RECORD	8
5.6 OVERTOPPING POTENTIAL	9
5.7 EVALUATION	9
6 STRUCTURAL STABILITY	10
6.1 EVALUATION OF STRUCTURAL STABILITY	10
7 ASSESSMENT/RECOMMENDATIONS	11
7.1 ASSESSMENT	11
7.2 RECOMMENDED MEASURES	11

APPENDIX

A.	PHOTOGRAPHS
B.	ENGINEERING DATA CHECKLIST
C.	VISUAL INSPECTION CHECKLIST
D.	HYDROLOGIC/HYDRAULIC ENGINEERING DATA AND COMPUTATIONS
E.	STABILITY ANALYSES
F.	REFERENCES
G.	DRAWINGS

PHASE 1 REPORT  
NATIONAL DAM SAFETY PROGRAM


Name of Dam:	Nanticoke Creek Watershed Protection Project Dam Site No. 8 I.D. No. NY-573 (#85D-3645)
State Located:	New York
County Located:	Broome
Watershed:	Susquehanna River Basin
Stream:	Unnamed tributary of Nanticoke Creek
Date of Inspection:	November 8, 1978

ASSESSMENT

The Nanticoke Creek Watershed Protection Project Dam Site No. 8 is a floodwater retarding structure. Examination of available documents and a visual inspection of the dam did not reveal conditions which are considered to be unsafe.

The total discharge capability of the spillways is adequate for the Probable Maximum Flood (PMF).

To assure the continued satisfactory performance of this structure, a schedule of periodic maintenance should be established. Included in this schedule should be items such as mowing the grass on the embankment slopes and periodic operation and lubrication of the slide gate mechanism.



George Koch  
Chief, Dam Safety Section  
New York State Department  
of Environmental Conservation  
NY License No. 45937

Approved By:



Col. Clark H. Benn  
New York District Engineer

17 April 79

Date:

---



NANTICOKE CREEK SITE No. 8 OVERVIEW  
NORTHERN END OF UPSTREAM FACE AND EMERGENCY SPILLWAY



OVERVIEW  
SOUTHERN END OF UPSTREAM FACE



PHASE 1 INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
NANTICOKE CREEK WATERSHED PROTECTION PROJECT  
DAM SITE No. 8  
I.D. No. NY 573  
(#85D-3645)  
SUSQUEHANNA RIVER BASIN  
BROOME COUNTY, NEW YORK

SECTION 1: PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase 1 Inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the National Dam Inspection Act, Public Law 92-367.

b. Purpose of Inspection

This inspection was conducted to evaluate the existing conditions of the dam, to identify deficiencies and hazardous conditions, to determine if these deficiencies constitute hazards to life and property, and to recommend remedial measures where required.

1.2 DESCRIPTION OF PROJECT

a. Description of the Dam and Appurtenant Structures

The Nanticoke Creek Watershed Protection Project Dam No. 8 consists of an earth dam with a principle spillway pipe passing through the embankment and an emergency spillway on the northern end of the dam.

The dam consists of a compacted earth embankment which is 41 feet high, has a crest length of 460 feet and a crest width of 16 feet. The upstream slope is 1 vertical on 3 horizontal and the downstream slope is 1 vertical on 2 1/2 horizontal. The crest and exposed slopes are grass covered. An earth cutoff trench of varying depth and width keys the embankment into the foundation soils.

The principle spillway consists of a two stage reinforced concrete drop inlet structure, a 24 inch diameter reinforced concrete water pipe with anti-seepage collars, and a plunge pool to dissipate energy at the outlet end of the conduit. A reservoir drain consisting of a 12 inch cast iron pipe extends from the upstream toe of the embankment to the base of the principle spillway riser. A vertical slide gate mechanism mounted along the inside of the riser controls the flow through the reservoir drain. The emergency spillway is a grass lined channel, 180 feet wide, located in an earth cut on the northern end of the dam.

An internal drainage system consisting of a gravel and sand filter with perforated 8 inch diameter bituminous coated, corrugated metal collector pipes is located at the base of the embankment near the downstream toe. Seepage is collected and conducted through this drain and outleted into the plunge pool.



b. Location

Dam No. 8 of the Nanticoke Creek Project is located on an unnamed tributary of the Nanticoke Creek, approximately 7.5 miles north of the Village of Maine. The site is off Howland Hill Road in the Town of Nanticoke, New York.

c. Size Classification

This dam is 41 feet high and is classified as an "intermediate" size dam (between 40 and 100 feet high).

d. Hazard Classification

The dam is classified in the "high" hazard category because of the presence of several homes downstream of the dam.

e. Ownership

This dam is owned by the County of Broome, New York.

f. Purpose of Dam

This dam is a floodwater retarding structure.

g. Design and Construction History

This dam was designed by the U.S. Department of Agriculture, Soil Conservation Service (SCS). Construction of the dam was completed in 1970. The SCS Office for Broome County, located at the Broome County Airport, has a design folder containing hydrologic, hydraulic, and structural design information, and the as-built plans and documents. Since the only modification made during construction was a minor one resulting from the rock surface under the spillway being deeper than anticipated, the plans included in Appendix F are essentially the same as the as-built drawings.

h. Normal Operating Procedures

Normal flows are discharged through the principle spillway. This structure has sufficient capacity to discharge a 100 year flood without flow occurring in the emergency spillway. For storms greater than the 100 year flood, flow will discharge through the emergency spillway.

1.3

PERTINENT DATA

a. <u>Drainage Area</u> (acres)	1382
b. <u>Discharge at Dam</u> (cfs)	
Principle Spillway W.S. at top of dam	70
Principle Spillway at Emergency Spillway Crest	66
Elevation	
Reservoir Drain at Principle Spillway Crest El.	18
Maximum Known Flood	61
Emergency spillway W.S. at top of dam	8280
c. <u>Elevation</u> (USGS datum)	
Top of Dam	1258.2
Emergency Spillway Crest (Auxiliary Spillway)	1252.5
Principle Spillway Crest (Service Spillway)	1239.5
Invert of Reservoir Drain Inlet	1218.0

- d. Reservoir (acres)
- |   |      |
|---|------|
| Surface area at Top of Dam                  | 46.2 |
| Surface area at Crest of Emergency Spillway | 33.0 |
| Surface area at Crest of Principle Spillway | 13.8 |
- e. Storage Capacity (acre-feet)
- |                          |      |
|--------------------------|------|
| Top of Dam               | 608  |
| Emergency Spillway Crest | 380  |
| Principle Spillway Crest | 88.6 |
- f. Dam
- Embankment Type: Compacted earth fill with  
an earth keyed cutoff trench
- |                              |                              |
|------------------------------|------------------------------|
| Embankment length (ft.)      | 460                          |
| Slopes Upstream              | 1 vertical on 3 horizontal   |
| Downstream                   | 1 vertical on 2.5 horizontal |
| Crest elevation (USGS datum) | 1258.2                       |
| Crest Width (ft)             | 16                           |
- g. Spillway
- Principle Spillway (Service)
- Type: Uncontrolled, reinforced concrete, two stage drop inlet (2 x 6 ft.) rising 24.5 feet; 24 inch diameter reinforced concrete pressure conduit 248 feet long; riprapped plunge pool.
- |                    |    |
|--------------------|----|
| Length (ft.): Weir | 12 |
|--------------------|----|
- Emergency Spillway (Auxiliary)
- Type: Grass-lined channel having trapezoidal cross-section
- |   |        |
|---|--------|
| Bottom Width (ft.)                        | 180    |
| Side Slopes (V : H)                       | 1 on 3 |
| Length of level section (in profile)(ft.) | 50     |
| Exit Slope (ft/ft)                        | 0.29   |
- h. Low Level Outlet
- Reservoir Drain:
- Type: 12 inch diameter cast iron pipe with a reinforced concrete inlet.
- Control: Mechanically operated vertical slide gate mounted along the inside of the principle spillway riser.

## SECTION 2: ENGINEERING DATA

### 2.1 DESIGN

#### a. Geology

The Nanticoke Creek Watershed Project Dam No. 8 is located in the "Glaciated Allegheny Plateau" physiographic province of New York State. Bedrock underlying the site is mapped as Cashaqua Shale of the Upper Devonian Age. This rock was formed approximately 400 million years ago.

Glacial ice was instrumental in smoothing the topography of the area. The present surficial deposits have resulted primarily from glaciations during the Cenozoic Era, the last of which was the Wisconsin glaciation, approximately 11,000 years ago. Glacial deposits such as outwash plains and eskers are major features of the landscape in parts of this region.

#### b. Subsurface Investigations

A subsurface investigation program was conducted by the Soil Conservation Service in 1966. This program consisted of 23 test pits and 13 drill holes. The maximum depth of the explorations was 34 feet. Applicable subsurface information is included in Appendix G.

In general, the surficial soils at the project site consist of a thin layer of topsoil underlain by glacial till on both abutments and by assorted alluvium and reworked till in the floodplain. A gravelly material with moderate to rapid permeability was encountered from 8 to 12 feet in Test Pit No. 1 on the northern abutment. This material was found only in this one test pit. Shale bedrock underlies these soil deposits.

#### c. Embankment and Appurtenant Structures

The dam was designed by the Soil Conservation Service who prepared a design report. Seventeen drawings, several of which have been included in Appendix G, were prepared for the construction of the dam.

Hydraulically, the dam was designed to retard the floodwaters resulting from a 100 year frequency storm, without a discharge occurring in the emergency spillway.

### 2.2 CONSTRUCTION RECORDS

Complete as-built contract plans and documents are available from the SCS Office in Broome County. No major construction changes were made on this job. The as-built plans were included in the appendix of this report.

### 2.3 OPERATION RECORD

Since the dam is an ungated, floodwater retarding structure, no operating records are maintained regarding water levels. However, during periods of heavy rainfall, SCS personnel do monitor reservoir levels.

### 2.4 EVALUATION OF DATA

The data presented in this report has been compiled from information obtained from the Soil Conservation Service as well as the New York State Department of Environmental Conservation files. It appears to be adequate and reliable for the purpose of the Phase 1 Inspection.



## SECTION 3: VISUAL INSPECTION

### 3.1 FINDINGS

#### a. General

Visual inspection of Dam Site No. 8 was conducted on November 8, 1978. The weather was clear and the temperature was around 50°F. The water surface was several inches above the invert of the low stage inlet on the riser. There was a small flow from the principle spillway pipe spilling into the plunge pool.

#### b. Embankment

The earth embankment showed no signs of distress. The vertical and horizontal alignment of the crest appears to be as it was constructed, with no visible surface cracks appearing on the crest or embankment slopes. There were no areas of serious sloughing or subsidence noted. Some minor sloughing was observed on the upstream slope in the range of fluctuation of the water surface level.

Inspection of the downstream face did not reveal any signs of seepage. There was a slight discharge from the 8 inch collection pipe of the internal drainage system on the southern side of the principle spillway pipe. The collection pipe to the north of the principle spillway was dry.

No undesirable vegetative growth or animal penetrations into the slopes were observed. However, on the date of the inspection, the grass on the upstream and downstream slope had not been mowed.

#### c. Principle Spillway

The principle spillway consists of the vertical drop inlet structure, a reinforced concrete pressure pipe through the embankment, a plunge pool and an outlet channel. All of these components were in satisfactory condition. The only minor deficiency noted concerned the plunge pool. The downstream toe of the dam, the bottom of the stream channel and the stream banks were lined with riprap, but there was no riprap in the center of the stream to check the velocity of water coming through the spillway pipe.

#### d. Emergency Spillway

A grass lined emergency spillway in an earth cut section is located beyond the northern end of the embankment. The spillway had been mowed and appeared to be in satisfactory condition.

#### e. Drain

The reservoir drain conduit and slide gate may be used to lower the reservoir when the pool level is below the principle spillway crest. The slide gate is located within a pipe sleeve which extends to the top of the riser.

f. Downstream Channel

The outlet channel beyond the end of the plunge pool was heavily overgrown with weeds and brush. However, no severe side-slope erosion or debris obstructions were in evidence.

g. Reservoir

There were no signs of soil instability in the reservoir area.

3.2

EVALUATION OF OBSERVATIONS

Visual observations did not reveal any problems which would adversely affect the safety of the dam.



#### SECTION 4: OPERATION AND MAINTENANCE PROCEDURES

##### 4.1 PROCEDURES

The normal water surface elevation is approximately at the low stage inlet elevation. Downstream flows are limited by the capacity of the 24 inch diameter reinforced concrete pipe. The reservoir provides 374 acre feet of storage between the normal water level and the crest of the emergency spillway.

##### 4.2 MAINTENANCE OF DAM

The dam is maintained by the owner and is in satisfactory condition. Normal maintenance consists of mowing the crest of the embankment and the bottom of the emergency spillway channel.

##### 4.3 WARNING SYSTEM IN EFFECT

No apparent warning system is present.

##### 4.4 EVALUATION

The dam and appurtenant structures are satisfactorily maintained.

## SECTION 5: HYDROLOGIC/HYDRAULIC

### 5.1 DRAINAGE AREA CHARACTERISTICS

Delineation of the watershed draining into the reservoir pool area was made using the USGS 7.5 minute quadrangle for Lisle, N.Y. The watershed consists of woodlands and lightly forested area situated in a rural section. Relief ranges from moderate to steep with the steeper slopes occurring on the western side of the watershed. The slopes on the western side range from 15 to 20%, and on the eastern side they range from 5 to 10%. The rectangularly shaped drainage area is about 1382 acres.

### 5.2 ANALYSIS CRITERIA

The analysis of the spillway capacity of the dam was performed using the Corps of Engineer's HEC-1 computer program, incorporating the "Snyder Synthetic Unit Hydrograph" method and the "Modified Puls" flood routing procedure. The spillway design flood selected for analysis was the PMF in accordance with recommended guidelines of the U.S. Army Corps of Engineers.

### 5.3 SPILLWAY CAPACITY

The principal and emergency spillways are uncontrolled structures. The principal spillway operates under weir or orifice flow conditions depending upon the floodwater inflow to the reservoir pool. During orifice flow operation, pressure flow develops in the 24 inch conduit. The emergency spillway was analyzed as a broad-crested weir having a discharge coefficient (C) of 3.087.

The spillways have sufficient capacity for discharging the peak outflow from the PMF. Due to the limited storage capacity, there will be little attenuation of the storm flows. For this storm, the peak inflow and the peak outflow are both 3640 cfs. When the spillways are discharging the peak outflow, the water surface will be 2.4 feet below the top of the dam.

### 5.4 RESERVOIR CAPACITY

Normal flood control storage capacity of the reservoir between the principal and emergency spillways is 291 acre-feet which is equivalent to a runoff depth of 2.5 inches over the drainage area. Surge storage capacity to the maximum high water elevation is an additional 228 acre-feet; equivalent to a runoff depth over the drainage area of 2.0 inches. Total storage capacity of the dam is 608 acre-feet; equivalent to 5.3 inches of direct runoff.

### 5.5 FLOODS OF RECORD

The maximum known flood occurred during Hurricane Eloise during September, 1975. The pool level at this time was reported to be about 7 feet above the principal spillway crest. The calculated discharge for this flood is as follows:

<u>Elevation (ft.)</u>	<u>Discharge (cfs)</u>
1246.4	61

5.6 OVERTOPPING POTENTIAL

Analysis indicates the total discharge capability is sufficient to prevent overtopping from the PMF.

5.7 EVALUATION

This dam has sufficient capability to impound and adequately discharge floodwaters expected to result from the PMF.



## SECTION 6: STRUCTURAL STABILITY

### 6.1 EVALUATION OF STRUCTURAL STABILITY

#### a. Visual Observations

No signs of major distress of the dam were observed during the inspection.

#### b. Design and Construction Data

Design data was obtained from the Soil Conservation Service Office in Binghamton. Stability analyses were performed by SCS using a modification of the Swedish Circle Method. Various conditions were analyzed during the design process. The conditions applicable to the dam as it was constructed are as follows:

<u>CONDITION</u>	<u>MINIMUM FACTOR OF SAFETY</u>	
	<u>UPSTREAM SLOPE</u>	<u>DOWNSTREAM SLOPE</u>
Full Drawdown	1.69	—
Long Term Steady State Seepage from Emergency Spillway Crest	—	1.60

The calculated factors of safety for this dam are in excess of the minimum factors in the Corps of Engineers recommended guidelines. The dam is therefore considered to have an adequate factor of safety for stability.

A summary of the analyses and sections showing the failure arcs are included in Appendix E.

Based on discussions with SCS representatives, the dam was built essentially according to the plans. The only significant difference was that the rock surface was somewhat deeper than expected.

#### c. Post Construction Changes

The SCS representatives were not aware of any changes which have been made on the dam.

#### d. Seismic Stability

This dam is located in Seismic Zone No. 1. Therefore, a seismic stability analysis is not warranted.

## SECTION 7: ASSESSMENT/RECOMMENDATIONS

### 7.1 ASSESSMENT

#### a. Safety

The Phase 1 Inspection of the Nanticoke Creek Dam No. 8 did not reveal conditions which constitute a hazard to human life or property. The earth embankment is considered to be stable, structurally, and capable of safely retarding floodwaters resulting from the PMF.

The design of this dam includes an internal drainage system to control the phreatic surface and to provide a safe outlet for foundation seepage.

#### b. Adequacy of Information

Information concerning the design and performance of this dam is considered adequate for the purposes required for Phase 1 Inspection Reports.

#### c. Need for Additional Investigations

No additional investigations are necessary at this time.

### 7.2 RECOMMENDED MEASURES

The following tasks should be undertaken by maintenance forces:

- a. Periodic operation and lubrication of the mechanically operated slide gate mechanism to insure the ease of operation of the reservoir drain conduit.
- b. A schedule for periodic maintenance should be established which would include items such as mowing the grass on the embankment slopes.



APPENDIX A


PHOTOGRAPHS



VIEW LOOKING EAST ALONG DAM CREST



EMERGENCY SPILLWAY LOOKING DOWNSTREAM




RISER - PRINCIPAL SPILLWAY INLET



PRINCIPAL SPILLWAY OUTLET PIPE  
AND PLUNGE POOL (LOOKING UPSTREAM)





PRINCIPAL SPILLWAY OUTLET PIPE  
AND PLUNGE POOL (LOOKING DOWNSTREAM)



OUTLET OF INTERNAL DRAINAGE  
SYSTEM COLLECTION PIPE

APPENDIX B

ENGINEERING DATA CHECKLIST



NANTICOKE CREEK  
 Name of Dam SITE 8  
 I.D. # NY-573  
 (85D-3645)

Check List  
 Engineering Data  
 Design Construction Operation

Item	Remarks		
Dam	Plans YES	Details YES	Typical Sections YES
Spillway(s)	YES	YES	YES
Outlet(s)	YES	YES	YES
Design Reports	YES		
Design Computations	YES		
Discharge Rating Curves			
Dam Stability	YES		
Seepage Studies	YES		
Subsurface and Materials Investigations	YES		

Item	Remarks
Construction History	ONLY INFORMATION AVAILABLE OBTAINED THROUGH DISCUSSIONS WITH PROJECT INSPECTOR
Surveys, Modifications, Post-Construction Engineering Studies and Reports	.. NONE REPORTED
Accidents or Failure of Dam Description, Reports	NONE REPORTED
Operation and Maintenance Records Operation Manual	NONE

APPENDIX C

VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST

1) Basic Data

a. General

Name of Dam NANTICOKE CREEK SITE 8

I.D. # N.Y. 573 (#850-3645)

Location: Town NANTICOKE County BROOME

Stream Name UNNAMED

Tributary of NANTICOKE CREEK

Longitude (W), Latitude (N) W 076° 4.8' N 42° 16.5'

Hazard Category C

Date(s) of Inspection 11/8/78

Weather Conditions SUNNY 45°-50°

b. Inspection Personnel R. WARRENDER; W. LYNICK

c. Persons Contacted H. HIRTH, SCS SYRACUSE

G. PAGE & D. KOLESAR, SES BROOME Co.

d. History:

Date Constructed 1970

Owner BROOME COUNTY

Designer SCS

Constructed by C.D. MURRAY

2) Technical Data

Type of Dam EARTH

Drainage Area 1382 ACRES

Height 41 ft. Length 460 ft

Upstream Slope 1 on 3 Downstream Slope 1 on 2.5



2) Technical Data (Cont'd.)

External Drains: on Downstream Face \_\_\_\_\_ @ Downstream Toe RIP RAP

Internal Components:

Impervious Core \_\_\_\_\_

Drains 8" CMP DRAIN PIPE IN SAND & GRAVEL DRAIN

Cutoff Type COMPACTED EARTH FILL

Grout Curtain \_\_\_\_\_

3) Embankment

EARTH FILL WITH GOOD VEGETATIVE COVER

a. Crest

- (1) Vertical Alignment OKAY
- (2) Horizontal Alignment OKAY
- (3) Surface Cracks NONE
- (4) Miscellaneous CREST WAS ONLY PART OF EMBANKMENT  
WHICH HAD BEEN MOWED.

b. Slopes

- (1) Undesirable Growth or Debris, Animal Burrows SLOPES HAD NOT  
BEEN MOWED
- (2) Sloughing, Subsidence or Depressions MINOR SLOUGHING ON UPSTREAM  
SLOPE AT WATER SURFACE ELEVATION (WITHIN RANGE OF  
FLUCTUATION)
- (3) Slope Protection UNMOWED GRASS AND CROWN VETCH
- (4) Surface Cracks or Movement at Toe NONE
- (5) Seepage NONE
- (6) Condition Around Outlet Structure SATISFACTORY

c. Abutments

(1) Erosion at Embankment and Abutment Contact NONE

(2) Seepage along Contact of Embankment and Abutment NONE

(3) Seepage at toe or along downstream face NONE

d. Downstream Area - below embankment

(1) Subsidence, Depressions, etc. NONE

(2) Seepage, unusual growth NONE

(3) Evidence of surface movement beyond embankment toe NO EVIDENCE

(4) Miscellaneous

e. Drainage System

2-8" DIAMETER BIT. COATED CMP IN SAND &  
GRAVEL DRAIN FILL

(1) Condition of relief wells, drains, etc. \_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

(2) Discharge from Drainage System VERY SLOW (LESS THAN

3 GAL/HOUR) \_\_\_\_\_  
\_\_\_\_\_



4) Instrumentation

(1) Documentation/Surveys N/A

(2) Observation Wells N/A

(3) Weirs N/A

(4) Piezometers N/A

(5) Other

5) Reservoir

a. Slopes TREES AND GRASS UP TO EDGE OF RESERVOIR

b. Sedimentation NONE

c) Spillways (including tail race channel)

- a. General RISER, OUTLET PIPE & PLUNGE POOL IN  
SATISFACTORY CONDITION
- b. Principle Spillway 24.5' HIGH RECTANGULAR RC DROP INLET;  
24" DIA RC PRESSURE PIPE; RIP RAP LINED PLUNGE  
POOL AT OUTLET
- c. Emergency or Auxiliary Spillway GRASS LINED TRAPEZOIDAL  
OPEN CHANNEL IN EARTH CUT
- d. Condition of <sup>OUTLET</sup> Tail race channel RIP RAP ON SIDES OF CHANNEL  
FORMED PLUNGE POOL - NO RIP RAP ACROSS CENTER OF  
CHANNEL TO CHECK VELOCITY OF FLOWS EXITING FROM  
SPILLWAY PIPE.
- e. Stability of Channel side/slopes NO SPECIAL TREATMENT  
BEYOND ENDS OF PLUNGE POOL; BRUSH & WEEDS  
GROWING ON CHANNEL BANKS.

7) Stream Channel

a. Condition (debris, etc.) TREES AND BRUSH LINING STREAM  
BANKS

b. Slopes 1 ON 1 - NOT RIPAPPED, ALTHOUGH SOME STONE  
PRESENT.

c. Approximate number of homes VILLAGE OF MAINE PLUS 3 HOMES  
NEAR THE POINT WHERE THE STREAM PASSES UNDER  
THE COUNTY HIGHWAY

8) Miscellaneous \_\_\_\_\_

9) Structural

a. Concrete Surfaces SATISFACTORY

b. Structural Cracking NONE

c. Movement - Horizontal & Vertical Alignment (Settlement) NONE

d. Junctions with Abutments or Embankments N/A

e. Drains - Foundation, Joint, Face N/A

f. ~~Water passages, conduits, sluices~~ SATISFACTORY

g. Seepage or Leakage NONE



h. Joints - Construction, etc. \_\_\_\_\_

i. Foundation \_\_\_\_\_

j. Abutments \_\_\_\_\_

k. Control Gates RESERVOIR DRAIN HAS SLIDE GATE

l. Approach & Outlet Channels \_\_\_\_\_

m. Energy Dissipators (plunge pool, etc.) PIPE EXTENSION  
SATISFACTORY

n. Intake Structures \_\_\_\_\_

o. Stability \_\_\_\_\_

p. Miscellaneous \_\_\_\_\_

APPENDIX D

HYDROLOGIC/HYDRAULIC

ENGINEERING DATA AND COMPUTATIONS

CHECK LIST FOR DAMS  
HYDROLOGIC AND HYDRAULIC  
ENGINEERING DATA

1

AREA-CAPACITY DATA:

	<u>Elevation</u> (ft.)	<u>Surface Area</u> (acres)	<u>Storage Capacity</u> (acre-ft.)
1) Top of Dam	<u>1258.2</u>	<u>46.2</u>	<u>608</u>
2) Design High Water (Max. Design Pool)	<u>1255.2</u>	<u>39.0</u>	<u>476</u>
3) Auxiliary Spillway Crest	<u>1252.5</u>	<u>33.0</u>	<u>380</u>
4) Pool Level with Flashboards	<u>N/A</u>	<u>          </u>	<u>          </u>
5) Service Spillway Crest	<u>1239.5</u>	<u>13.8</u>	<u>88.6</u>

DISCHARGES

	<u>Volume</u> (cfs)
1) Average Daily	<u>N/A</u>
2) Spillway @ Maximum High Water	<u>70.1</u>
3) Spillway @ Design High Water	<u>67.8</u>
4) Spillway @ Auxiliary Spillway Crest Elevation	<u>65.6</u>
5) Low Level Outlet	<u>18.7</u>
6) Total (of all facilities) @ Maximum High Water	<u>8350.2</u>
7) Maximum Known Flood	ELEV. = <u>1246.4</u>

CREST:

ELEVATION: 1258.2Type: LEVEL; GRASSED EARTHWidth: 16 ft. Length: 460 ft.Spillover N/A

Location \_\_\_\_\_

SPILLWAY:

PRINCIPAL

EMERGENCY

1239.5Elevation 1252.5RC DROP INLET W/TRASH RACKType TRAPEZOIDAL CHANNEL2ft x 6ftWidth 180ft 1 on 3 SLOPES

Type of Control

✓

Uncontrolled

✓

Controlled:

N/A

Type

N/A

(Flashboards; gate)

N/A

Number

N/AN/A

Size/Length

N/A

Invert Material

MOWED GRASSAnticipated Length  
of operating service< 1 PER 100 YRS24" DIA RC CONDUIT - 248' LONG

Length

600ft.SHARP CRESTEDHeight Between Spillway Crest  
& Approach Channel Invert  
(Weir Flow)N/ABROAD CRESTEDL/b = 1.0WEIR LENGTH = 12'



~~OUTLET STRUCTURES/EMERGENCY DRAINAGE~~ FACILITIES: -RESERVOIR DRAIN

Type: Gate ✓ Sluice \_\_\_\_\_ Conduit ✓ Penstock \_\_\_\_\_

Shape : GATE - FLAT CIRCULAR CONDUIT - ROUND CAST IRON

Size: \_\_\_\_\_

Elevations: Entrance Invert 1215.5

Exit Invert 1210.5

Tailrace Channel: Elevation 1208.5

HYDROMETEROLOGICAL GAGES:

Type : NONE

Location: \_\_\_\_\_

Records:

Date - \_\_\_\_\_

Max. Reading - \_\_\_\_\_

FLOOD WATER CONTROL SYSTEM:

Warning System: NONE

Method of Controlled Releases (mechanisms):

NONE EXCEPT FOR MANUALLY OPERATED RESERVOIR  
DRAIN SLIDE GATE

WATERAGE AREA: 1382 ACRES 2.16 SQ.MI.

WATERAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: LIGHT FOREST & WOODLANDS

Terrain - Relief: MODERATE TO STEEP

Surface - Soil: GLACIAL TILL

Runoff Potential (existing or planned extensive alterations to existing  
(surface or subsurface conditions)

NONE

Potential Sedimentation problem areas (natural or man-made; present or future)

NONE

Potential Backwater problem areas for levels at maximum storage capacity  
including surcharge storage:

NONE

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the  
Reservoir perimeter:

Location: NONE

Elevation: \_\_\_\_\_

Reservoir:

Length @ Maximum Pool N/A (Miles)

Length of Shoreline (@ Spillway Crest) N/A (Miles)

## NOTES ON DAM #8

D.A. = Drainage area in square miles

L = River mileage from the given station to the upstream limits of the drainage area

LCA = River mileage from the station to the center of gravity of the drainage area

PMP = Probable Maximum Precipitation in inches

$t_p$  = Lag time from mid-point of unit rainfall duration,  $t_r$ , to peak of unit hydrograph, in hours.

$t_r$  = Unit rainfall duration, equal to  $\frac{t_p}{5.5}$ , in hours.

$C_t$  = Coefficient depending upon units and drainage basin characteristics

$t_r$  = Unit rainfall duration other than standard unit;  $t_r$  adopted in specific study, in hours.

$t_{pr}$  = lag time from mid-point of unit rainfall duration,  $t_r$ , to peak of unit hydrograph, in hours

D.A. = 2.16 square miles, L = 3.33 miles, LCA = 1.32 miles

PMP = 20.5 inches  $C_t = 2.0$

$C_p = 0.625$  from average 640  $C_p = 400$

$$t_p = C_t (L \cdot LCA)^{0.3} = 2.0 [(3.33)(1.32)]^{0.3} = 3.12 \text{ hours}$$

$$t_r = \frac{t_p}{5.5} = \frac{3.12}{5.5} = .57 \text{ hours (Use 1 hr. } t_r \text{ hydrograph)}$$

$$t_{pr} = t_p + 0.25(t_r - t_p) = (3.12) + .25(1 - .57) = 3.23 \text{ hrs.}$$

From HMR 33 - Figure 2, Deple - Area - Duration  
Zone I Prec. = 20.5"

6 hour % 111 = 22.55, 12 hour % 133 = 27.26

24 hour % 122 = 25.01, 48 hour % 142 = 29.11



## PROJECT GRID

JOB NAIT-COKE CREEK SITE 8	SHEET NO. 1	CHECKED BY	DATE
SUBJECT HYDROLOGY & HYDRAULIC COMPUTATIONS		COMPUTED BY RLW	DATE 1/30/79

PRINCIPAL SPILLWAY CAPACITY

WATER SURFACE AT AUXILIARY SPILLWAY CREST

$$q = A \sqrt{\frac{2gH}{1 + K_e + K_b + K_d L}} = 3.14 \sqrt{\frac{2(32.2)(41)}{1 + .5 + .45 + (.0165)(248)}} = 65.64 \text{ cfs}$$

WATER SURFACE AT DESIGN HIGH WATER

$$q = 3.14 \sqrt{\frac{2(32.2)(43.7)}{1 + .5 + .45 + (.0165)(248)}} = 67.77 \text{ cfs}$$

WATER SURFACE AT TOP OF DAM

$$q = 3.14 \sqrt{\frac{2(32.2)(46.7)}{1 + .5 + .45 + (.0165)(248)}} = 70.06 \text{ cfs}$$

EMERGENCY SPILLWAY CAPACITY

WATER SURFACE AT TOP OF DAM

$$q = CLH^{3/2} = (3.087)(197.1)(5.7)^{3/2} = 8280.1 \text{ cfs}$$

$$L = 180 + (2.95)(3)(2) = 197.1$$

RESERVOIR DRAIN CAPACITY

WATER SURFACE AT PRINCIPAL SPILLWAY CREST

$$q = .78 \sqrt{\frac{2(32.2)(24.5)}{1 + .5 + 0 + .0417(30)}} = 18.68 \text{ cfs}$$



## PROJECT GRID

JOB	NANT COKE CREEK SITE 3	SHEET NO.	2	CHECKED BY		DATE	
SUBJECT	HYDROLOGY & HYDRAULIC COMPUTATIONS			COMPUTED BY	RLW	DATE	2/2/77

DEPTH OF FLOW IN EMERGENCY SPILLWAY DURING PMF

$$Q = CLH^{3/2} \Rightarrow H^{3/2} = \frac{Q}{CL} = \frac{3577}{(3.087)(189)} = 6.13 \Rightarrow H = 3.35'$$
$$Q = 3643 - 66 = 3577$$
$$L = 180 + (1.5)(3)(2) = 189$$

\*\*\*\*\*  
 HEC-1 VERSION DATED JAN 1973  
 UPDATED AUG 74  
 CHANGE NO. 01  
 \*\*\*\*\*

MAINTICREEK CREEK WATERSHED PROJECT SITE NO 8  
 PMF WITH RATIOS  
 DATE

JOB SPECIFICATION  
 NU NHR I:MIN IDAY IHR I:MIN METRC IPLT IPRT NSTAN  
 100 1 0 0 0 0 0 0 0  
 JUPER 5 NWT 0

MULTI-PLAN ANALYSES TO BE PERFORMED  
 NPLAN= 1 NRTIO= 2 LRATIO= 1  
 RTIOS= 0.50 1.00

\*\*\*\*\* \*\*\*\*\* \*\*\*\*\* \*\*\*\*\*

SUB-AREA RUNOFF COMPUTATION  
 ISTAQ ICOMP IFCON I:TAPE JPLT JPRT INAME  
 1 0 0 0 0 0 0  
 HYDROGRAPH DATA  
 IHDG IING TAKEA SHAP TRSDA TRSPC RATIO ISNDW ISAME LOCAL  
 1 1 2.16 0. 2.16 0. 0. 0. 0. 0. 0. 0.

PRECIP DATA  
 SPFE PMS R6 R12 R24 R48 R72 R96  
 0. 20.50 111.00 122.00 133.00 142.00 0. 0. 0.  
 TRSPC COMPUTED BY THE PROGRAM IS 0.738

LOSS DATA  
 STRKR DLTKR RTIOL ERAIN STRKS RTIOK STRTL CNSTL ALSMX RTIMP  
 0. 0. 1.00 0. 0. 1.00 1.00 0.10 0. 0.

UNIT HYDROGRAPH DATA  
 TP= 3.00 CP=0.63 NTA= 0

RECESSION DATA  
 STATQ= 4.00 QRCNS= 4.00 RTIOR= 1.00  
 APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 3.71 AND R= 2.44 INTERVALS

UNIT HYDROGRAPH 15 END-OF-PERIOD ORDINATES, LAG= 2.98 HOURS, CP= 0.63 VOL= 1.00  
 47. 153. 269. 8. 5. 3. 93. 62. 41. 27.  
 14. 12.

END-OF-PERIOD FLOW  
 TIME RAIN EXCS COMP Q  
 1 0.01 0. 4.  
 2 0.01 0. 4.  
 3 0.01 0. 4.

10	0.02	0.	4.
11	0.02	0.	4.
12	0.02	0.	4.
13	0.11	0.	4.
14	0.14	0.	4.
15	0.17	0.	4.
16	0.43	0.01	4.
17	0.15	0.06	8.
18	0.12	0.02	17.
19	0.01	0.	26.
20	0.01	0.	29.
21	0.01	0.	25.
22	0.01	0.	18.
23	0.01	0.	13.
24	0.01	0.	10.
25	0.11	0.01	9.
26	0.11	0.01	9.
27	0.11	0.01	11.
28	0.11	0.01	13.
29	0.11	0.01	15.
30	0.11	0.01	17.
31	0.23	0.18	25.
32	0.23	0.18	53.
33	0.23	0.18	98.
34	0.28	0.18	145.
35	0.29	0.18	181.
36	0.28	0.18	205.
37	1.69	1.58	286.
38	2.01	1.91	540.
39	2.52	2.42	1003.
40	6.33	6.23	1757.
41	2.35	2.25	2731.
42	1.65	1.75	3507.
43	0.17	0.07	3640.
44	0.17	0.07	3111.
45	0.17	0.07	2323.
46	0.17	0.07	1613.
47	0.17	0.07	1097.
48	0.17	0.07	756.
49	0.	0.	528.
50	0.	0.	369.
51	0.	0.	253.
52	0.	0.	167.
53	0.	0.	107.
54	0.	0.	67.
55	0.	0.	31.
56	0.	0.	17.
57	0.	0.	9.
58	0.	0.	7.
59	0.	0.	6.
60	0.	0.	5.
61	0.	0.	5.
62	0.	0.	4.
63	0.	0.	4.
64	0.	0.	4.
65	0.	0.	4.
66	0.	0.	4.
67	0.	0.	4.



72	0.	0.	4.
33	0.	0.	4.
34	0.	0.	4.
85	0.	0.	4.
86	0.	0.	4.
87	0.	0.	4.
38	0.	0.	4.
39	0.	0.	4.
90	0.	0.	4.
91	0.	0.	4.
92	0.	0.	4.
93	0.	0.	4.
94	0.	0.	4.
95	0.	0.	4.
96	0.	0.	4.
97	0.	0.	4.
98	0.	0.	4.
99	0.	0.	4.
100	0.	0.	4.

SUM 21.52 17.84 25082.

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
3640.	2845.	1024.	347.	25084.
	12.25	17.64	17.92	18.00
	1411.	2032.	2065.	2074.

HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 1

2.	2.	2.	2.	2.
2.	2.	2.	2.	14.
7.	5.	5.	6.	8.
47.	73.	91.	102.	879.
1820.	1555.	1162.	806.	185.
54.	33.	16.	9.	3.
2.	2.	2.	2.	2.
2.	2.	2.	2.	2.
2.	2.	2.	2.	2.
2.	2.	2.	2.	2.

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
1820.	1422.	512.	173.	12542.
	6.13	8.82	8.96	9.00
	706.	1016.	1032.	1037.

HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 2

4.	4.	4.	4.	4.
4.	4.	4.	4.	29.
13.	10.	9.	11.	17.
93.	145.	181.	205.	1757.
3640.	3111.	2323.	1613.	1003.
107.	67.	31.	17.	528.
4.	4.	4.	4.	6.
4.	4.	4.	4.	4.
4.	4.	4.	4.	4.
4.	4.	4.	4.	4.

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
3640.	2845.	1024.	347.	25084.
	12.25	17.64	17.92	18.00

CFS  
INCHES  
AC-FT





353.	349.	344.	339.	335.	331.	327.	323.	279.
311.	307.	303.	300.	296.	293.	289.	286.	253.
275.	273.	270.	267.	264.	261.	258.	255.	228.
247.	245.	242.	240.	237.	235.	232.	230.	226.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	3645.	2875.	904.	325.	23442.
INCHES		12.39	13.57	16.80	16.83
AC-FT		1426.	1794.	1935.	1938.

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

# PEAK FLOW SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS

## RATIOS APPLIED TO FLOWS

STATION	PLAN	0.50	1.00
1	1	1820.	3640.
2	2	0.	0.
1	1	1940.	3645.
2	2	0.	0.

OGRAPIH AT

ED TO

APPENDIX E  
STABILITY ANALYSES



2 -- W. S. Atkinson -- 10/1/66

Ray S. Decker

Subj: ENG 22-5, New York WP-06, Nanticoke Creek, Site No. 8

- C. Slope Stability Analysis: The analysis is limited to the embankment assuming that soft foundation soils are removed to elevation 1211 and replaced with embankment soils. The method of analysis is a modification of the Swedish circle.

A 3:1 upstream slope with 10 ft berm is adequate assuming drawdown to the base.

In the steady seepage case with the phreatic line from the emergency spillway crest to the downstream slope, the factor of safety is 1.5 for a 2 1/2:1 slope and 10 ft wide berm. The factor of safety is 1.6 with a drain at  $c/b = 0.6$  and no berm.

Shear values from sample 66W1301, Site 13, resulted in higher factors of safety than those from sample 67W735.

#### CONCLUSIONS AND RECOMMENDATIONS

- A. Preparation: Remove deleterious and soft material from the foundation.
- B. Cutoff and Drainage: Interrupt disturbed surface soils on the abutments with a partial cutoff. Cut off the permeable alluvial gravels labeled "B" on Form SCS-35B to till or bedrock. A 30 ft bottom width is suggested through the narrow floodplain to keep the hydraulic gradient near 1.0.

A trench drain is recommended to pick up seepage that bypasses the cutoff into alluvial gravels downstream. Extend the drain up both abutments to permanent pool level taking it to bedrock in the right abutment. A transverse drain (or lateral) can be placed against the sandy silt should this material (labeled "G") be continuous downstream. Drain filter elements can be designed in the field.


#### EMBANKMENT

- A. Placement of Material: Soils represented by samples tested can be placed anywhere in the embankment.

Standard density of the minus 3/4 inch fraction of samples 67W735 and 67W736 is about 124 pcf, correcting density of the minus No. 4 fraction for 15% rock. This agrees well with similar samples from Site No. 13 which had minus 3/4 inch standard densities of 123 and 123.5 pcf. It is concluded that compaction control for this site can be based on 95% of standard density using either the minus No. 4 or the minus 3/4 inch fraction.



202-1057  
 Continuation of Sheet 1012  
 Monticello Creek Site #3  
 New York





APPENDIX F

LIST OF REFERENCES




APPENDIX F

REFERENCES

- 1) U.S. Department of Commerce, Technical Paper No. 40, Rainfall Frequency Atlas of the United States, May 1961.
- 2) H.W. King and E.F. Brater, Handbook of Hydraulics, 5th edition, McGraw-Hill, 1963.
- 3) University of the State of New York, Geology of New York, Education Leaflet 20, Reprinted 1973.
- 4) Elwyn E. Seelye, Design, 3rd edition, John Wiley and Sons, Inc., 1960

APPENDIX G


DRAWINGS



# VICINITY MAP

NANTICOKE CREEK WATERSHED PROTECTION PROJECT,  
DAM SITE No. 8






DAM SITE

TOPOGRAPHIC MAP  
NANTICOKE CREEK WATERSHED PROTECTION PROJECT  
DAM SITE No. 8





# BENCH MARK DESCRIPTION

\* PALE IN SCS STANDARD ALUMINUM DISC  
18" ABOVE GROUND IN 14" DBH WHITE  
PINE TREE 280.0' DOWNSTREAM FROM E  
OF DAM ELEV 1214.82

**AS BUILT**  
8/25/70

## LEGEND

- DESIGN HIGH WATER
- CREST OF EMBANKMENT
- SEEDING POOL
- 6" STREAM
- COUNTRY LINES
- RIDGE LINE
- BENCH MARK
- TRAPLINE STATIONS
- CONSTRUCTION LIMITS
- DRAIN HOLES
- TEST PIT (LOGGED & SAMPLED)
- TEST PIT (LOGGED ONLY)
- FENCE LINE (ENCLOSURE)
- AS BUILT

## CURVE DATA

### LAYOUT DATA FOR CURVE I

$\Delta = 42^\circ 34'$   $T = 68.17$   
 $R = 175'$   $E = 12.87$   
 $D = 32.44'$   $M = 11.94'$   
 $L = 130.0'$

STATION	DEFLECTION	CHORD DIST
2+10	0	0.0
2+40	4.38	10.0
2+55	5.44	25.0
2+10	9.49	25.0
1+85	15.45	25.0
1+60	16.00	25.0
1+40	22.47	20.0

### LAYOUT DATA FOR CURVE II

$\Delta = 62^\circ 53'$   $T = 125.34$   
 $R = 205'$   $E = 35.28$   
 $D = 27.57'$   $M = 30.17'$   
 $L = 225'$

STATION	DEFLECTION	CHORD DIST
4+25	8	0.0
4+50	5.30	25.0
4+75	6.55	25.0
5+00	10.25	25.0
5+25	13.58	25.0
5+50	17.28	25.0
5+75	20.58	25.0
6+00	24.27	25.0
6+25	27.57	25.0
6+50	31.25	25.0

**FOUNDATION EXCAVATION IN FLOOD PLAIN**  
 REMOVE THE SILTY, SOFT GRAY TILL AND ORGANIC  
 MATTER WITHIN THE BASE OF THE DAM AS REPRESENTED  
 BY MATERIAL "B" ON SHEET 15.



2' CONTOUR INTERVALS

**NANTICOKE CREEK WATERSHED PROJECT**  
**SITE 8**

FLOODWATER RETARDING DAM  
 BROOME COUNTY, NEW YORK

**PLAN OF STRUCTURAL WORKS**

**U. S. DEPARTMENT OF AGRICULTURE**  
**SOIL CONSERVATION SERVICE**

Designed by: **JOSEPH**

Drawn by: **ANGEL**

Date:

Date:

Sheet:

Sheet:

NY-2006-P


2



**SECTION OF CUTOFF TRENCH AT STA 3+00**  
 (TYPICAL FROM APPROX STATION 2+65 TO 4+00 AND FROM  
 STA 5+75 TO APPROX. STA 7+20)


**SECTION OF CUTOFF TRENCH AT STA 4+25**  
 (TYPICAL FROM STATION 4+00 TO 4+50 AND 5+25 TO 5+75)

**SECTION OF CUTOFF TRENCH**  
 (TYPICAL FROM STATION 4+50 TO 5+25)








**CUTOFF TRENCH CONSTRUCTION NOTES**

1. FINAL DEPTH OF TRENCH TO BE DETERMINED AT TIME OF CONSTRUCTION BY THE ENGINEER.
2. EXCAVATE 10' MIN. INTO FIRM SHALE WHERE TRENCH BOTTOMS ON SHALE. ALL ROCK EXPOSED IN THE BOTTOM OF TRENCH SHALL BE THOROUGHLY CLEANED OF LOOSE MATERIAL PRIOR TO BACKFILLING OPERATION.




**EXCAVATION**  
 FOUNDATION  
 CORE (L&M)  
 CORE (L&M)  
 THE DAM  
 ARMED ROSS CUTWAY  
 INLET  
 COLLAR BOTTOMS

**TOTAL**  
 4  
 DAM &  
 LEVEL  
 CORE  
 CORE  
 PRIOR



PROFILE ALONG E LEVEL



PROFILE SCALE ALONG E LEVEL & EMERGENCY SPILLWAY

ELEVATION	
FOUNDATION	2592.2 ✓
CORE (C&M)	1506.8 ✓
CORE (C&M)	201.9 ✓
TOP DRAIN	64.5 ✓
AVERAGE RISE OUTLET	938.9 ✓
SWEEP	12.2 ✓
COLLAR BOTTOMS	1.0 ✓

TOTAL 6010.4 Cu Yds

EARTH FILL	
DAK. FOUNDATION	1805.6 ✓
LEVER	1500.9 ✓
CORE (C&M)	1506.8 ✓
CORE (C&M)	201.9 ✓
PRIM. SPW.	30.0 ✓


SUBTOTAL 5143.9

ADJUSTMENTS 202.0

TOTAL 5345.9 Cu Yds

NANTICOKE CREEK WATERSHED PROJECT			
SITE 8			
FLOODWATER RETARDING DAM			
BROOME COUNTY, NEW YORK			
CUTOFF TRENCH & EMERGENCY SPWY EXCAVATION			
U. S. DEPARTMENT OF AGRICULTURE			
SOIL CONSERVATION SERVICE			
Designed by	D. ZOGRAPOS	Date	1/67
Drawn by	B. FELTON	Date	1/67
Checked by	B. J. B.	Date	2/67
Project No.			NY-2006-P






SECTION OF DAM AT STA. 4+77 (TYPICAL FROM APPROX. STA. 2+58 TO 7+30)  
(NOT TO SCALE)

MATERIAL	
1	SILTY GRAVEL LABELLED M8
2	SHEET 15 AND REPRESENTED
3	TP-202 FROM 2
4	TP-305 FROM 2
5	TP-104 FROM 1

- 1 THE PLAN  
2 A. MAIN POWER  
B. MAIN OVER  
BE G  
3 A. MAIN  
B. USE  
4 WATER  
5 A. FOR  
B. USE  
CONT
- 1 THE FOUR  
2 COMPACT  
EXCAVATE  
AND USE  
3 TOPSOIL  
BE INCON



#### PRINCIPAL SPILLWAY EXCAVATION DETAILS

- 1 EXCAVATE THROUGH WEATHERED ROCK ALONG PRINCIPAL SPILLWAY.  
2 EXCAVATE UP LINE INTO FIRM SHALE WHERE TRENCH BOTTOMS ON SHALE. ALL ROCK EXPOSED IN THE BOTTOM OF TRENCH SHALL BE THOROUGHLY CLEANED OF LOOSE MATERIAL PRIOR TO PLACEMENT OF CONCRETE AND BACKFILLING OPERATION.

EXCAVATE MIN. 5' INTO ROCK

PRINCIPAL

DM 30'

ML

GM

SH

# AS BUILT

7/15/70

EARTH FILL REQUIREMENTS					
MATERIAL 1/	MAX. 2/ ROCK SIZE	MAX. 2/ LIFT THICK 3/	MINIMUM WATER CONTENT 4/	COMPACTION 5/	
				CLASS	DEFINITION
SILTY GRAVEL LABELLED MATERIAL "A" ON SHEET 15 AND REPRESENTED BY: TP-202 FROM 2.5' TO 10.0' TP-203 FROM 2.5' TO 10.0' TP-104 FROM 1.5' TO 10.0'	6"	9"	2 PERCENTAGE POINTS BELOW OPTIMUM MOISTURE	A	95% MAX. DENSITY BY ASTM D698 METHOD A



- 1/ THE PLACEMENT TABLE INDICATES ESTIMATED USE OF MATERIAL.
- 2/
  - A. MAXIMUM ROCK SIZE PLACED IN BACKFILL COMPACTED BY MEANS OF HAND TAMPING OR MANUALLY DIRECTED POWER TAMPERS OR PLATE VIBRATORS SHALL BE 3".
  - B. MAXIMUM ROCK SIZE OF 12" DUMPED IN THE EARTH FILL CAN BE RAKED TO THE PORTION OF THE DAM LABELLED "OVERSIZE ROCK SECTION" AS SHOWN ON THIS SHEET. OVERSIZE MATERIAL (6" TO 12") IN THIS SECTION SHALL BE GRADED SO THAT THE LARGER ROCK ARE PLACED TOWARD THE DOWNSTREAM SLOPE.
- 3/
  - A. MAXIMUM LIFT THICKNESS PRIOR TO COMPACTION.
  - B. USE 18" LIFTS IN AREAS WHERE OVERSIZE MATERIAL (6" TO 12") IS PLACED.
- 4/ WATER CONTENT AT TIME OF COMPACTION.
- 5/
  - A. FOR TYPICAL COMPACTION CURVES SEE SHEET 15.
  - B. USE CLASS V COMPACTION (SEE CONSTRUCTION SPECIFICATION 5) IN AREAS OF THE OVERSIZE ROCK SECTION CONTAINING OVERSIZE MATERIAL (6" TO 12").

## CONSTRUCTION DETAILS

1. THE FOUNDATION SURFACE THROUGH THE BASE AREA OF THE DAM SHALL BE SCARIFIED TO A DEPTH OF 6" AND COMPACTED PRIOR TO PLACEMENT OF FILL MATERIAL.
2. EXCAVATED MATERIAL (REPRESENTED BY TP 501 FROM 2.5' TO 90') IN FOUNDATION TRENCH SHALL BE STOCKPILED AND USED AS EARTH FILL ADJACENT TO THE DRAIN FILL MATERIAL. MINIMUM COVERING OF THIS MATERIAL SHALL BE 2.0' TOPSOIL THAT IS SUITABLE FOR USE AND NOT USED ON THE SPECIFIED AREA OF THE EMERGENCY SPILLWAY SHALL BE INCORPORATED WITHIN THE SLOPES OF THE EARTH FILL AS DIRECTED BY THE ENGINEER.



ON DETAILS  
ROCK ALONG

PAVE WHERE  
ROCK  
TRENCH SHALL  
USE MATERIAL  
SITE AND



NOV. 1969	EARTH FILL REQUIREMENTS	
DATE	ITEM	APP'D
REVISIONS		
NANTICOKE CREEK WATERSHED PROJECT		
SITE B		
FLOODWATER RETARDING DAM		
BROOME COUNTY, NEW YORK		
FILL PLACEMENT & PRIN. SPILLWAY EXCAVATION		
U.S. DEPARTMENT OF AGRICULTURE		
SOIL CONSERVATION SERVICE		
Designed	Date	App'd
L.C. BERTSON	1/67	
Drawn		
D. ANGELD	1/67	
Transd		
Checked		
B. J. G.	2/67	
		NY-2006-B






### **SMALL ANIMAL GUARD DETAILS**

(2 REG)




OUTLET DRAIN  
(SEE PROFILE)



### PLAN VIEW

0 0 2 3

SCALE IN FT



QUANTITY	SUMMARY
----------	---------

6 CULVDS. DRAIN TILE  
3 1/4" TIGHT SECTION  
2 1/4" TIGHT SECTION  
1 1/4" TIGHT SECTION  
METAL END CAPS




HEAT SEATING

1990

**AS BUILT** 7/25/70

## DRAINAGE SYSTEM NOTES

- ### MAINTENANCE SYSTEM NOTES
1. ALL DRAIN PIPE SHALL CONFORM TO SPECIFICATION 110 AND SHALL BE 8" DIA. SHAPE I; CLASS I (ANNULAR CORRUGATIONS) OR CLASS II (HELICAL CORRUGATIONS); TYPE-A (FULLY BITUMINOUS COATED) PIPE.
  2. USE A MINIMUM OF 12" OF DRAIN FILL AROUND PIPES.
  3. THE PROFILES AT THE BOTTOM OF ALL EXCAVATIONS AS SHOWN ARE ONLY APPROX THE REQUIRED FINISHED GRADES WILL BE ESTABLISHED IN THE FIELD AT THE TIME OF CONSTRUCTION BY THE ENGINEER.
  4. DRAIN FILL AT AREA OF DOWN STREAM SLOPE OF DAM TO BE COVERED WITH 18" RIPRAP.



DRAIN SIZE DISTRIBUTION GRAPH FOR DRAIN FILL

[illegible]


NAHTICUKE CREEK WATERSHED PROJECT  
SITE 8  
FLOODWATER RETARDING DAM  
BROOME COUNTY, NEW YORK  
DRAINAGE SYSTEM

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

Date	Time	Approved By
L C EATSON	1/87	
Drove BRUCE FELTON	1/87	
Present WIL TOLTON	1/87	
Clerk		
B J G	2/87	

NY-2000-P






ONE 12" LENGTH WITH FLANGE DETAIL SHEET B

200' OF STRAIGHT PIPE (CAST IRON)

USE STANDARD MECHANICAL JOINTS  
PIPE SHALL CONFORM TO SPEC 300  
AND SHALL BE 12" DIA. THICKNESS  
CLASS I

TOTAL COST IRON 278 L.F.

TOP OF CONSTRUCTED FILL  
TOP OF SETTLED FILL ELEV 12582




PROFILE ALONG & OF PRINCIPAL SPILLWAY

0 5 10 20 40 FEET  
HORIZ SCALE  
0 5 10 FEET  
VERT SCALE

ALL RIPRAP SHALL  
BE OF 18" TO 24" DIA.  
PERCENT AND  
WEIGHT OF THE  
6" AND 12" DIA.


# AS BUILT

9/25/70



STATION	PIPE	JUNCTION	DIST FROM OUTLET	INVERT OF 24" DIA PIPE
10+00	1/2"	OUTLET	0	1210.70
10+00	1/2"	J-1	16	1210.80
10+00	1/2"	J-2	32	1211.07
10+00	1/2"	J-3	48	1211.27
10+00	1/2"	J-4	64	1211.46
10+00	1/2"	J-5	80	1211.50
10+00	1/2"	J-6	96	1212.20
10+00	1/2"	J-7	112	1212.57
10+00	1/2"	J-8	128	1212.87
10+00	1/2"	J-9	144	1213.16
10+00	1/2"	J-10	160	1213.46
10+00	1/2"	J-11	176	1213.76
10+00	1/2"	J-12	192	1214.09
10+00	1/2"	J-13	208	1214.35
10+00	1/2"	J-14	224	1214.64
10+00	1/2"	J-15	240	1214.95
10+00	1/2"	J-16	248	1215.00

ABOVE DIMENSIONS FOR LENGTHS OF PIPE ARE BASED ON NOMINAL LENGTHS AND DO NOT INCLUDE CREEP.




COLLAR	DISS FROM OUTLET	INVERT OF 24" DIA PIPE
I	82	1212.02
II	106	1212.46
III	130	1212.90
IV	154	1213.35
V	178	1213.79
VI	202	1214.23
VII	226	1214.68

## 24" REINFORCED CONCRETE PIPE STRENGTH REQUIREMENTS

1. PRESSURE - 45 PSI
2. LOAD 33,387 LBS PER LIN FT BASED ON O.D. OF PIPE
3. MIN. 3 EDGE BEARING STRENGTH FOR 0.001 CRACK 12,599 LBS PER LIN FT FOR PRE-STRESSED PIPE (AASHTO C-301)

WHERE THE PIPE FURNISHED HAS AN OUTSIDE DIAMETER GREATER THAN THAT CALLED FOR ON THE PLANS, THE EDGE BEARING STRENGTH OF THE PIPE FURNISHED MUST BE EQUAL TO OR GREATER THAN THE SPECIFIED THREE EDGE BEARING STRENGTH MULTIPLIED BY THE RATIO OF THE OUTSIDE DIAMETER OF THE PIPE FURNISHED TO THE OUTSIDE DIAMETER SPECIFIED.




FABRICATION INSTRUCTIONS	
(1) 4.0' SECTIONS (2) 8.0' SECTION ONE (1) SPIGOT RING WALL FITTING FOR 10" WALL	<del>(1) 20.0' SECTIONS</del> <del>(2) 8.0' SECTION</del> <del>ONE (1) SPIGOT RING</del> <del>WALL FITTING FOR</del> <del>10" WALL</del>
PIPE SUPPLIER'S NOTE: CAST OUTSIDE OF SPIGOT RING WITH CONCRETE ON ONE 4.0' SECTION	<del>PIPE SUPPLIER'S NOTE:          CAST OUTSIDE OF SPIGOT          RING WITH CONCRETE ON          ONE 20.0' SECTION</del>

**RIPRAP DETAILS**  
 ALL RIPRAP SHALL BE GRADED FROM A MAX SIZE OF 18" TO A MIN SIZE OF 3" A MIN OF FORTY (40) PERCENT AND A MAX OF SIXTY (60) PERCENT (BY WEIGHT) OF THE ROCK RIPRAP SHALL BE BETWEEN 6" AND 12" IN SIZE.

13.06.70s RIPRAP

NANTICOKE CREEK WATERSHED PROJECT  
 SITE E  
 FLOODWATER CONTROL DAM  
 BROOME COUNTY NEW YORK  
 PLAN PROFILE OF DAM  
 U. S. DEPARTMENT OF AGRICULTURE  
 SOIL CONSERVATION SERVICE  
 D. ZOGHARIS 1/67  
 W. E. GRAY JR 1/67  
 NY-2006-P






OUTSIDE FACE INSIDE FACE


SECTION A-A

AS DIRECTED BY ENGINEER, STEEL IN SHADED AREA WILL BE CUT, BENT, OR MOVED AS REQUIRED TO ACCOMMODATE REPAIR OR DRAIN FOR EXACT LOCATION OF POND DRAIN SEE SHEET 2A



OUTSIDE FACE INSIDE FACE


UPSTREAM ELEVATION



STEEL 3' FROM BOTTOM OF FOOTING

STEEL 2' FROM TOP OF FOOTING

FOOTING PLAN



OUTSIDE FACE INSIDE FACE

DOWNSTREAM ELEVATION


0 2 4 6  
SCALE IN FEET



AS BUILT


9/25/70

PLATE CONSTRUCTION  
JOINT



STEEL 2" FROM INSIDE FACE OF RISER  
AND 2" FROM TOP OF FOOTING

SIDEWALL ELEVATION



STEEL 2" FROM OUTSIDE FACE OF RISER  
AND 3" FROM BOTTOM OF FOOTING

SIDEWALL ELEVATION

NANTICOKE CREEK WATERSHED PROJECT  
SITE B

FLOODWATER RETARDING DAM  
BROOME COUNTY, NEW YORK

RISER STRUCTURAL DETAILS


U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

Drawn by: B. J. G.

Scale: 1/4" = 1'-0"


NY 2006-P

1/2" Preformed Joint Filler  
18" wide, Type I (Spec. 106)





### REINFORCED CONCRETE ANTI-SEEP COLLAR

7 - Req'd




### CONCRETE BEDDING

(WITH REINFORCED CONC BEDDING SUPPORT)



### REINFORCED CONCRETE WATER PIPE JOINT




### RESERVE DRAIN CONCRETE BEDDING

Length ①

**AS BUILT**

9/25/90



**CONCRETE BEDDING**  
(WITH NON-REINFORCED CONC.  
SECTION OF BEDDING SUPPORT)

Mark	Size	Length	Type	Quan. / Collar	Total Quan.	Total Length
A-1	4	1 - 3	1	4	28	35-0
A-2	4	4 - 9	1	8	56	265-0
A-3	4	3 - 3	1	8	56	182-0
A-4	4	10 - 9	1	2	14	130-6

Mark	Size	Length	Type	Total Ques.	Total Length
D-1	5	9-3	1	4	37-0
D-2	5	2-8	1	10	26-8

## STEEL

No. 4 Bar 63-6 • 23 LDU

No. 5 Bar 63-8 • 64


ADDITIONAL NO. 4 BARS USED WHERE ROCK EXPLAN.  
IS 1 FOOT LOWER THAN DESIGN

CONCRETE 159-5 = 105 LBS

Reinforced  Ca. Yds.

Non-Reinforced 25.5 Cu Yds.

CONSTRUCTION DETAILS SHEET B



SPIGOT RING WALL FITTING

NANTICOKE CREEK WATERSHED PROJECT  
SITE 8  
FLOODWATER RETARDING DAM  
BROOME COUNTY, NEW YORK  
CONDUIT DETAILS

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

Designated L C 100-TSCA  
D. ANGELO  
Room 117 - 100-TSCA

50

Figure 10


22

NY-2006-8




# **SHILL MULE LOGS**

**BH 351, Emr. Spill., Elev. 1228.1**




**BH 354, Emr. Spill., Elev. 1231.3**




NOTE: Some indications of sand, or smaller till in the 12' depth zone.

**BH 355, Emr. Spill., Elev. 1260.4**




**BH 357, Prin. Spill., Elev. 1215.3**






NOTE: Horizons shown from 0-6.2 inferred from log of T.F. 302.


**BH 352, Prin. Spill., Elev. 1218.3**




## **TYPICAL COMPACTION CURVES**



COMPACTION CURVE FOR MATERIAL  
FROM TP-202 2' TO 10' DEEP  
LABORATORY CLASSIFICATION CL



COMPACTION CURVE FOR MATERIAL  
FROM TP-205 2' TO 10' DEEP  
LABORATORY CLASSIFICATION CL



**THE BELL SYSTEM**

Construction of dam	1 - 99
Barrow area	101 - 199
Emergency spillway	201 - 299
Construction of outlet structures	301 - 399
Barrow channel	401 - 499
Outlet works	501 - 599

## REVIEWED SOIL CLASSIFICATION SYSTEM SYMBOLS

- CU Well graded gravel; gravel-sand mixtures
- CU Poorly graded gravel
- CU Silty gravel; gravel-sand-silt mixtures
- GC Clayey gravel; gravel-sand-silt mixtures
- CU Well graded sands; sand-gravel mixtures
- CU Poorly graded sands
- CU Silty sands; sand-silt mixtures
- SC Clayey sands; sand-silt mixtures
- CU Silts; silty, v. fine sands; sandy or clayey silts
- CL Clays of low to medium plasticity; silty, sandy or gravelly clays
- CU Clays of high plasticity; fat clays
- ME Elastic silts; micaceous or diatomaceous silts
- CU Organic silts and organic silty clays of low plasticity
- CU Organic clays or silts of medium to high plasticity

**INDEX**

B	Basalt	22	Schist
Ch	Chert	23	Shale
Gr	Granite	24	Siltstone
La	Limestone	25	Slate
Ma	Marble	26	Sandstone

**摘要**

- 28 Disturbed  
 25 Dad's disturbed  
 Carr HX Carr

EX-79 (Rev. 1-25-60)

- Number of blows required for 1-ft. standard penetration, using 140" (4.0) split barrel sampler, 140 lb. hammer, and 30" drop. ASTM D 1586.
- 9.0 Depth to hole (ft.)
- CL Unified Soil Classification System
- 12.0
- dry barrel sampler
- Soiler hit to advance hole by wash boring
- 17.0 Depth to hole
- Soil core, 3-1/8" diameter
- Percent rock core recovery in each drill run
- La Breda Rock Sampler
- W (Water) Water Level

NANTICOKE CREEK WATERSHED PROJECT  
SITE 8  
FLOODWATER RETARDING DAM  
BROOKE COUNTY, NEW YORK  
LOGS OF TEST HOLES

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

Contract	2-2 ELUS	Date	Approved By
Station			Title
Project			
County			
State			
Section			
Range			
Township			
Section			
County			
State			
Contract	2-2	Date	Approved By
Station			Title
Project			
County			
State			
Section			
Range			
Township			
Section			
County			
State			

# **GENERAL DESCRIPTION**

**A**  
Gravel, silty - approximately 40 percent fines, 20 percent sand and 40 percent + 4 - occasional 6" - 12" subangular flake - brown, sometimes grading to a slightly olive cast with depth - coarse to wet with depth - slowly permeable - glacial till - very dense. (OH)

**B**  
Gravel, or silt (typically an assumed alluvium) frequent logs and other organic remains - brown and sometimes gray - generally accreted - very slowly to moderately permeable - recent alluvium and recent till - generally soft or loose. (OH & HL)

**C**  
Shale - grading toward a siltstone - moderately thin bedded with some clay seams near the surface - weathered approximately a foot - dense and hard with depth - average water loss per 5" of 10 holes: 16 psi - 30 psi, 20 psi - 1.7 psi - gray to grayish brown - occasional minor artesian pressure. (OH)

**D**  
Gravel, silty - approximately 25 percent fines, 25 percent sand and 50 percent + 4 - some 6" - 12" flaggy cobbles - gray - saturated - slowly permeable - glacial till - dense. (OH)

**E**  
Silt, some sand (10-15 percent) - brown - moist to wet - slowly permeable - glacial lacustrine - soft to medium density. (HL)

**F**  
Gravel, some sand and few fines - many 10" - 20" flaggy cobbles and fairly well graded ("best" of boulders?) - brown - moist - moderate to rapidly permeable - very dense (bouldery consistency). (OH)

**G**  
Silt, very sandy - brown - moist to wet - moderately permeable - glacial lacustrine - medium density. (HL)

**H**  
Silt, some sand and high in organic matter (floodplain silt and topsoil mixture) - dark brown - moist - slowly permeable - recent alluvium - soft to medium density. (HL)

## **BACK-UP PIT LOGS**

### **TP 1, C/L, Elev. 1240.2**

0	1.0	Topsoil	(OH)
1.0	8.0	Material A	(OH)
8.0	12.0	Material F	(OH)

NOTE: This material is essentially the same as the predominant brown till on this site, except that it has a considerable concentration of cobbles and boulders. Possibly some sort of ice-contact feature.

### **TP 2, C/L, Elev. 1219.2**

NOTE: SEE PROFILE ON SHEET II

### **TP 3, C/L, Elev. 1216.3**

0	1.0	Topsoil - Material H	(HL)
1.0	4.0	Material B	(OH & HL)
4.0	+	Material C	(SH)

### **TP 4, C/L, Elev. 1216.4**

0	1.0	Topsoil - Material H	(HL)
1.0	3.0	Material B	(OH & HL)
3.0	+	Material C	(SH)

### **TP 5, C/L, Elev. 1215.1**

0	2.3	Material B	(OH & HL)
2.3	+	Material C	(SH)

### **TP 6, C/L, Elev. 1216.0**

0	1.0	Topsoil	(OH)
1.0	11.0	Material A	(OH)
11.0	+	Material C	(SH)

### **TP 7, C/L, Elev. 1217.1**

0	1.0	Topsoil	(OH)
1.0	10.0	Material A	(OH)

### **TP 8, C/L, Elev. 1217.0**

0	1.0	Topsoil	(OH)
1.0	10.0	Material A	(OH)

# **TP 9, C/L, Elev. 1217.0**

0	1.0	Topsoil	(OH)
1.0	11.0	Material A	(OH)

# **TP 10, C/L, Elev. 1217.1**

0	1.0	Topsoil	(OH)
1.0	11.0	Material A (P.S. 104.1)	(OH)

# **TP 11, C/L, Elev. 1217.1**

0	1.0	Topsoil	(OH)
1.0	11.0	Material A	(OH)

# **TP 12, C/L, Elev. 1217.0**

0	1.0	Topsoil	(OH)
1.0	11.0	Material A (P.S. 102.1)	(OH)

# **TP 13, C/L, Elev. 1217.3**

0	1.0	Topsoil	(OH)
1.0	10.0	Material A	(OH)

# **TP 14, C/L, Elev. 1217.0**

0	1.0	Topsoil	(OH)
1.0	12.0	Material A	(OH)

# **TP 15, C/L, Elev. 1216.9**

0	1.0	Topsoil	(OH)
1.0	12.0	Material A (P.S. 105.1)	(OH)

# **TP 16, C/L, Elev. 1216.4**

0	1.0	Topsoil	(OH)
1.0	12.5	Material A - very minor seepage at the 6' depth	(OH)

# **TP 17, C/L, Elev. 1216.3**

0	1.5	Topsoil (Floodplain silt) - Material B	(OH & HL)
1.5	3.5	Material B	(OH & HL)
3.5	+	Material C	(SH)

# **TP 18, C/L, Elev. 1216.3**

0	2.0	Topsoil (Floodplain silt) (P.S. 102.1)	(OH)
2.0	4.7	Material B	(OH)
4.7	+	Material C	(SH)

# **TP 19, C/L, Elev. 1214.0**

0	1.5	Topsoil (Floodplain silt) - Material B	(OH)
1.5	4.0	Material B	(OH)
4.0	7.0	Material A, except drab color (P.S. 101.1)	(OH)

# **TP 20, C/L, Elev. 1216.7**

0	1.0	Topsoil	(OH)
1.0	3.5	Material B, some Material D mixed in	(OH & HL)
3.5	6.0	Material B (P.S. 104.1)	(OH)
6.0	7.5	Material A, except drab color	(OH)

# **TP 21, C/L, Elev. 1217.4**

0	1.5	Topsoil (Floodplain silt) - Material B	(OH)
1.5	4.0	Material B	(OH)
4.0	5.0	Material C (unweathered)	(SH)
5.0	+	Material C	(SH)

# **TP 22, C/L, Elev. 1216.7**

0	2.5	Material B (P.S. 101.1)	(OH & HL)
2.5	9.0	Material B (quite loose in place and saturated - some seepage waters of pit showing minor coloring) (P.S. 101.2)	(OH)

# **TP 23, C/L, Elev. 1217.5**

0	1.0	Topsoil	(OH)
1.0	2.0	Material A	(OH)
2.0	+	Material C	(SH)

## **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**


### **TP 24, C/L, Elev. 1218.1**

### **TP 24, C/L, Elev. 1218.1**




# TEST HOLE LOG


NO. 11, C.A. (Shallow), Elev. 1220.7




NO. 151, Barrow, Elev. 1244.1



NO. 151, Barrow, Elev. 1244.4



NO. 151, Barrow, Elev. 1244.4



Quantity of Soil	Weight
Gravel	100 - 100
Coarse sand	100 - 100
Medium sand	100 - 100
Fine sand	100 - 100
Silt	100 - 100
Clay	100 - 100

## SOIL CLASSIFICATION SYMBOLS

- GW Well graded gravel; gravel-sand mixture
- GP Poorly graded gravel
- GM Silty gravel; gravel-sand-silt mixture
- GC Clayey gravel; gravel-sand-clay mixture
- GW Well graded sand; sand-gravel mixture
- GP Poorly graded sand
- GM Silty sand; sand-silt mixture
- GC Clayey sand; sand-clay mixture
- ML Silty clay, n. fine sand; sandy or silty silt
- CL Clay of low to medium plasticity; silty, sandy or gravelly clay
- CH Clay of high plasticity; fat clay
- ML Silty silt; silty sand or silty clay
- CL Clay of low to medium plasticity; silty, sandy or gravelly clay
- CH Clay of high plasticity; fat clay
- ML Silty silt; silty sand or silty clay
- CL Clay of low to medium plasticity; silty, sandy or gravelly clay
- CH Clay of high plasticity; fat clay

## SOIL SYMBOLS

GW	Gravel	ML	Silty silt
GP	Poorly graded gravel	MC	Clayey silt
GM	Silty gravel	CL	Clay of low to medium plasticity
GC	Clayey gravel	CH	Clay of high plasticity
GW	Well graded sand	ML	Silty silt
GP	Poorly graded sand	MC	Clayey silt
GM	Silty sand	CL	Clay of low to medium plasticity
GC	Clayey sand	CH	Clay of high plasticity

## NOTES

- GW Gravel
- GP Poorly graded gravel
- GM Silty gravel
- GC Clayey gravel
- GW Well graded sand
- GP Poorly graded sand
- GM Silty sand
- GC Clayey sand
- ML Silty silt
- CL Clay of low to medium plasticity
- CH Clay of high plasticity

## TEST TO DETERMINE SOIL CLASSIFICATION

- 1. Number of blows required for 1-ft. standard penetration, using 140 lb. hammer, and 30" drop.
- 2. 9.0 Depth in hole (ft.)
- 3. Unified Soil Classification Symbol
- 4. 12.0
- 5. Dry barrel sampler
- 6. 17.0 Depth in hole
- 7. Back core, 2-1/8" diameter
- 8. Payson rock core recovery in each drill run
- 9. 30.0
- 10. 30.0
- 11. 30.0
- 12. 30.0
- 13. 30.0
- 14. 30.0
- 15. 30.0
- 16. 30.0
- 17. 30.0
- 18. 30.0
- 19. 30.0
- 20. 30.0
- 21. 30.0
- 22. 30.0
- 23. 30.0
- 24. 30.0
- 25. 30.0
- 26. 30.0
- 27. 30.0
- 28. 30.0
- 29. 30.0
- 30. 30.0
- 31. 30.0
- 32. 30.0
- 33. 30.0
- 34. 30.0
- 35. 30.0
- 36. 30.0
- 37. 30.0
- 38. 30.0
- 39. 30.0
- 40. 30.0
- 41. 30.0
- 42. 30.0
- 43. 30.0
- 44. 30.0
- 45. 30.0
- 46. 30.0
- 47. 30.0
- 48. 30.0
- 49. 30.0
- 50. 30.0
- 51. 30.0
- 52. 30.0
- 53. 30.0
- 54. 30.0
- 55. 30.0
- 56. 30.0
- 57. 30.0
- 58. 30.0
- 59. 30.0
- 60. 30.0
- 61. 30.0
- 62. 30.0
- 63. 30.0
- 64. 30.0
- 65. 30.0
- 66. 30.0
- 67. 30.0
- 68. 30.0
- 69. 30.0
- 70. 30.0
- 71. 30.0
- 72. 30.0
- 73. 30.0
- 74. 30.0
- 75. 30.0
- 76. 30.0
- 77. 30.0
- 78. 30.0
- 79. 30.0
- 80. 30.0
- 81. 30.0
- 82. 30.0
- 83. 30.0
- 84. 30.0
- 85. 30.0
- 86. 30.0
- 87. 30.0
- 88. 30.0
- 89. 30.0
- 90. 30.0
- 91. 30.0
- 92. 30.0
- 93. 30.0
- 94. 30.0
- 95. 30.0
- 96. 30.0
- 97. 30.0
- 98. 30.0
- 99. 30.0
- 100. 30.0

NANTICOKE CREEK WATERSHED PROJECT  
SITE 8  
FLOODWATER RETARDING DAM  
BROOME COUNTY, NEW YORK  
LOGS OF TEST HOLES

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

Log by B.S. ELLIS

Date

Sheet

B.S. ELLIS

2/57

15

NY-2006-P